

EXHIBIT C

2024 CAMBRIA FIRE DEPARTMENT FIRE HAZARD FUEL REDUCTION PROGRAM POLICY

SCOPE OF SERVICES

All parcels that are placed on the Cambria Community Services District annual “Fire Hazard Fuel Reduction Program” shall adhere to the following criteria:

All clearance work must be completed by July 15, 2024. If the parcel does not conform to the requirements as stated in the notice sent to the property owner, **the parcel will go on the CCSD’s contract list on July 25, 2024.** The CCSD’s Contractor will then be directed to abate the parcels on the contract list to the following standards:

- Limit leaves, needles, twigs, bark, cones, pods, and chips to three inches (3”) in depth.
- Weeds and annual grasses should not exceed four inches (4”) in height. Avoid exposing bare soil or creating a situation that would encourage erosion.
- Remove Scotch/Irish or other broom type plants, Pampas Grass, Jubata Grass and Crocosmia, also known as Fire Weed. Isolated specimens may be left with greater than ten feet (10’) separation and all dead materials are removed.
- All down dead trees, tree rounds or limbs within thirty feet (30’) of any structure must be removed. Tree stumps fallen over shall be cut and retain no more than 6 feet (6’) of the log within this thirty-foot (30’) zone.
- All down trees twelve inches (12”) in diameter or greater beyond thirty feet (30’) from any structure may remain on the parcel. However, the entire trunk must be completely on the ground. Materials less than twelve inches (12”) in diameter shall be cut and removed from the property.
- Remove ladder vegetation (dead wood) from under trees and shrubs, maintaining six feet (6’) of vertical clearance for trees greater than twenty feet (20’) in height.
- Remove combustible construction debris, trash and rubbish from property.
- Protect seedling pines, oaks and native shrubs by flagging them prior to cutting weeds.

OTHER CONDITIONS

- The Contractor shall photograph each parcel with a digital camera (as directed by the CCSD Fire Department) before and after abatement. Pictures shall be taken from the same spot, incorporating the same view. The before and after pictures shall include all flagged vegetation. Pictures shall include the date and the Assessor’s Parcel Number (APN) on the picture. All pictures will be named using the Assessor’s Parcel Number (APN) and the letters B or A, to indicate before (B) or after (A) clearance. The Contractor shall provide a digital photo file in a .jpg format which is compatible with CCSD software (thumb drive, etc.).
- All internal combustion powered equipment shall have approved and functional spark arresters on the exhaust.
- A fire extinguisher (ABC type) of at least five (5) pounds capacity shall be immediately available at the work site. A minimum of two and one half (2½) gallons of water must be available for vegetation fire extinguishment at all times by portable means. Examples are a pressurized water extinguisher, Hudson type pump sprayer or back-pump.
- All abatement work assigned to the CCSD Contractor shall begin no later than July 26, 2024, and must be completed August 26, 2024.
- All parcels shall be completely abated as prescribed to the property line, street and adjoining easements.

- ALL MATERIAL REMOVED FROM ALL PARCELS SHALL BE HAULED AWAY OR APPROVAL WILL BE DENIED, however tree limbs/rounds should not be removed from the Cambria area due to Pine Pitch Canker control requirements.

DEBRIS SHALL NOT BE DUMPED ON ADJOINING OR UNCLEARED PORTIONS OF LOTS. ANY EVIDENCE OF ILLEGAL DUMPING WILL BE PROSECUTED TO THE FULLEST EXTENT OF THE LAW.